

**SOUTH VAN HORNE HOUSING ENABLING PROJECT**

**ADDENDUM #1**

The following addendum is issued to address revisions to the original Contract Documents.

THE FOLLOWING REVISIONS SHALL BE CONSIDERED AS PART OF THE CONTRACT DOCUMENTS AND ALL COSTS THERETO SHALL BE INCLUDED IN THE BID PRICE.

**Contract Specifications:**

**1. Section 01001 – Special Provisions**

**ADD:**

**23. Soil Disposal**

None of the excavated material is to be reused for backfilling purposes. All excess soil shall be transported to one of the two City properties, depending on the quality of the material.

The approved disposal locations are:

- Old Landfill Site (Gordon Road) – 49.77848, -92.86466
- Snow Dump Location (Durance Ave) – 49.7881629, -92.8176491

The City will assess the quality of the material onsite and advise which of the above locations the material is to be transported to.

The City is currently assessing the impacts of O. Reg. 406/19 (On-Site and Excess Soil Management). Any additional hauling, testing, documentation, or regulatory compliance requirements arising from this regulation will be addressed as a change in work.

**2. Section 01000 – General Requirements**

The entirety of Section 1.9 - Contract Administrator's Site Office is to be added to the tender form (as a provisional item):

|      |  |    |   |
|------|--|----|---|
| 1.57 | Consultant's Site Office (PROVISIONAL) | LS | 1 |
|------|--|----|---|

**Contract Drawings:**

**3. Drawing D-101, Process – Proposed Lift Station Plans and Sections**

**DELETE:**

Bill of Material, Item 1 – 2150 dia pre-cast concrete lift station (Supply N.I.C.)

**REPLACE WITH:**

Bill of Material, Item 1 – 2150 dia pre-cast concrete lift station