

Addendum #02

Project:	Duke Street Reconstruction		
Date:	2026-02-18	Contract No.:	T-2026-3
Distribution:	City of Dryden Bids and Tenders, MERX	KGS Group Project No.:	25-1512-001

Receipt of this addendum shall be acknowledged in the submission of the completed tender. This addendum shall form part of the contract. Please check your tender to include or deduct the work outlined in this addendum. The tenders submitted without this addendum included shall be registered as an invalid tender submission.

1.0 GENERAL

1.1 GENERAL REQUIREMENTS

This Addendum shall be attached to the Specifications and Drawings and shall form an integral part of the Contract Documents. The contents of this Addendum shall be brought to the attention of all concerned.

2.0 DESIGN CHANGES

Item B6 a) in the Schedule of prices shall be revised from "New 525mm corrugated HDPE pipe" and replaced with "New 525mm reinforced concrete pipe"

This item shall conform to CSA A257.2 and OPSS.MUNI 1820

The section of pipe to be replaced will be at 3+511.99, and will be the south tie in between Kirkpatrick Ave and New San. MH#6

3.0 SPECIFICATIONS

3.1 Bid Form

1. Delete: Bid Form Schedule of Prices
2. Add: Revised Bid Form Schedule of Prices – See attached

4.0 QUESTIONS AND ANSWERS

4.1 Questions

1. Q: Does the 200mm watermain require a cross/connection to 300mm watermain as there is no item or is it to be included in Item D12.

A: Please include within item D12

2. Q: Does Item E13 require dual wall/smooth interior w/sock CSA182.2 or flexible single wall w/sock

A: Please refer to section 2.6 of Sewer Specifications and Section 2.5 of Roadway Specifications in the contract documents

3. Q: Do we know the size of pipe for lowering for Item F6 in the provisionals.

A: The size for the watermain lowering in Schedule of Prices Item F5 is assumed to be 200mm

4. Q: There is a high pressure gas main within the extents of this project. Are we required to have third party present when working around this main?

A: The Contractor is responsible to notify the local gas authority prior to the commencement of any work, which may affect the pipes belonging to the gas utility company. Should the local gas authority require a representative on site, the Contractor will provide access.

5. Q: Is it possible to move the contract closing date so it is not at the exact same day and time as Dryden's other contract, South Van Horne Housing Enabling Project?

A: The Tender closing date and time will remain the same.

6. Q: can you please clarify if the City of Dryden would impose any tipping fees for the asbestos containing materials and any contaminated soils?

A: Tipping fees will be waived for materials disposed of as part of this contract.

7. Q: Please clarify if the "designated area" identified on page 5 of 21, 3.3. Disposal of Excavated Material .4 is the final resting place for the excavated material or is that a site where material is to be stockpiled and then tested?

A: The City is currently assessing the impacts of O. Reg. 406/19 (On-Site and Excess Soil Management). The proponents are to include fees for excavation and disposal of excavated material within 10km of the project site. Any fees associated with additional hauling, testing, documentation, or regulatory compliance requirements arising from O.Reg 406/19 will be addressed as a change in work.

END OF ADDENDUM #2